COORDINATES			
PT. NO.	STATION W/OFFSET	NAD 83 EAST (X)	NAD 83 NORTHING (Y)
	532+00N 300L	2,474,999.66	457,314.86
	516+00N 300L	2,473,441.32	456,953.34
	502+00N 300L	2,472,077.81	456,637.11
	502+00N 300R	2,472,213.32	456,052.71
	496+20.39N 320L	2,471,458.42	456,514.05
	496+20.39N 340R	2,471,711.24	455,895.20
	485+00N 320L	2,470,458.79	455,904.13
	3+00 185L	2,471,823.07	455,939.26
	2+98.49 190L	2,471,468.29	456,511.05
	2+98.49 210L	2,471,448.56	456,507.98
	12+68.19 210L	2,471,305.08	457,427.76
	12+68.19 190L	2,471,324.29	457,434.51
	14+55.27 210L	2,471,250.06	457,523.64
	14+55.27 190L	2,471,265.62	457,536.73
	23+20.22 190L	2,470,661.60	458,041.08
	28+68.22 190L	2,470,204.79	458,160.61
	28+68.22 160L	2,470,207.08	458,191.11
	33+76.72 190L	2,469,666.69	458,094.47
	33+76.72 160L	2,469,674.24	458,125.50
	37+26.72 190L	2,469,278.52	458,349.49
	37+26.72 160L	2,469,309.25	458,371.03
	40+20 190L	2,469,100.95	458,622.26
	40+20 160L	2,469,125.67	458,639.29

SHEET INDEX



LEGEND

BUILDING
FENCE
GUARD RAIL
TREE LINE
INDIVIDUAL TREE
POWER POLE
LIGHT POLE
WATER
WALL
RETAINING WALL
SHRUB
BRUSH-MARSH LINE
POST
PAVED ROAD
UNPAVED ROAD
NAVAID GREEN — G-46
NAVAID RED — R-45

H&V CONTROL
U S HIGHWAY
STATE HIGHWAY
ROAD NUMBER — 30

ANCHORAGE — A
WRECK — W
MONUMENT — M

NOTES:
1. SOUNDINGS ARE IN FEET AND TENTHS AND REFER TO MEAN LOWER LOW WATER.
2. HORIZONTAL DATUM IS NAD 1983.
3. THE SOUNDINGS ON THIS DRAWING ONLY INDICATE THE GENERAL CONDITION OF THE CHANNEL ON THE DATE OF SURVEY.
4. DATE OF SURVEY: 7 NOV. 2011 CONDITION

E 2,468,000 E 2,469,000 E 2,470,000 E 2,471,000 E 2,472,000 E 2,473,000 E 2,474,000

N 460,000 N 459,000 N 458,000 N 457,000 N 456,000

US Army Corps of Engineers
Charleston District

No.	Base Block Description	Appv.	Date	No.	Base Block Description	Appv.	Date
No. 1	Base Block Description 1	Appv. 1	Date 1	No. 9	Base Block Description 9	Appv. 9	Date 9
No. 2	Base Block Description 2	Appv. 2	Date 2	No. 10	Base Block Description 10	Appv. 10	Date 10
No. 3	Base Block Description 3	Appv. 3	Date 3	No. 11	Base Block Description 11	Appv. 11	Date 11
No. 4	Base Block Description 4	Appv. 4	Date 4	No. 12	Base Block Description 12	Appv. 12	Date 12
No. 5	Base Block Description 5	Appv. 5	Date 5	No. 13	Base Block Description 13	Appv. 13	Date 13
No. 6	Base Block Description 6	Appv. 6	Date 6	No. 14	Base Block Description 14	Appv. 14	Date 14
No. 7	Base Block Description 7	Appv. 7	Date 7	No. 15	Base Block Description 15	Appv. 15	Date 15
No. 8	Base Block Description 8	Appv. 8	Date 8	No. 16	Base Block Description 16	Appv. 16	Date 16
MARK	DESCRIPTION	APPRV.	DATE	MARK	DESCRIPTION	APPRV.	DATE

Date:	26 NOV. 2011
Design file no.	9401
Drawing	Dynamic Circle
File name:	
Plot date:	
Dwg. scale:	1" = 200'

SURVEYED BY:
Drawn by: MRV
Reviewed by:
Oked by:
Submitted by:

U.S. ARMY ENGINEER DISTRICT
CORPS OF ENGINEERS
CHARLESTON, SOUTH CAROLINA

ATLANTIC INTRACOASTAL WATERWAY
STA. 482+32N TO STA. 531+12N AIWW
STA. 0+45 TO STA. 42+80 JEREMY CREEK
9401
GEORGETOWN AND CHARLESTON COUNTIES

SHEET 1 OF 1